

LOAD LIFTER-SOLUTIONS, LLC



2009 OTR-P

Call for pricing (F.E.T. Not Included)
OTR-P Modular Home Transport with Lift Capacity
Terms & Delivery: 1/3 with Order, 1/3 upon Completion of Main Frame
Balance Due on Delivery 12 to 16 Weeks from Receipt of Deposit
Freight: FOB Petoskey, MI

SPECIFICATIONS

80,000 lbs. G.V.W.R. 4-Axle
Main Frame 14" X 6" X .375" Rect. Tube
Cross-Members 12' X 20.7# Channel
Side Tie-Downs
Ship-Loose Pocket
D.O.T. Approved Lighting and Taping
Length - 48 ft. (Extends to 75 ft.)
Width - 8.5 ft. (Extends to 16 ft.)
Working Deck - 40 ft. (Extends to 67 ft.)
Deck Height - 32 inches

RUNNING GEAR

Four Axles - 22,500# Rating, 77.5" Track, 5" Round Axle
Suspension - H-9700 4-Axle with Leaf Spring
Brakes- ABS System, Automatic Slack Adjusters
Hub & Drums Cast Hubs & Steel Drums, 10-Hole, Single Nut
Wheels - 6.75" X 17.5 10-Hole Disc, Weight Capacity 4,540 lbs.
Fifth Wheel Towing Hook Options
Lifting Mechanism Goodyear Air Brakes
Synchronized for Independent 5" Lift
Four Independently Controlled Air/Hydraulic Lift Cylinders
Kingpin Lift Assembly Independent of Trailer Frame

COMPONENTS

Main Frame 14' X 6" X .375" Rect. Tube
Cross-Members 12" X 20.7# Channel
Outriggers Main Tube - 6" X 3" X .188" Rect. Tube
Outriggers Inner Tube - 5" X 25" X .188" Rect. Tube

www.loadlifter-solutions.com